

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MACOMB</u> (County)	Located In: <u>CHESTERFIELD</u>	Corner Code # <u>B-1</u>
1. Public Land Survey	T <u>3N</u> R <u>13E</u>	<u>B-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling In Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, ROBERT H. BIRKETT, in a field survey on JULY 22, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1818, W. PRESTON, DISTANCE AND MONUMENT NOT DETERMINED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET CORNER USING RECORD DISTANCES FROM ADJOINING PROPERTY DESCRIPTIONS ON THE LINE BETWEEN C-13 AND B-13 LENOX TOWNSHIP, T. 4 N., R. 14 E.


DISTANCE B-1 TO A-1  
 G.L.O. 40 CHAINS  
 FIELD (GRID) 2702.44'

DISTANCE B-1 TO C-1  
 G.L.O. 40 CHAINS  
 FIELD (GRID) 2689.06'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 3/4" X 24" IRON WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, B-1, 41094" IN MONUMENT BOX.

- AZ. 85° - 221.61' - SET P.K. NAIL W/MONUMENTATION TAG IN SOUTH FACE UTILITY POLE.
- AZ. 190° - 31.17' - SET P.K. NAIL W/MONUMENTATION TAG IN EAST FACE UTILITY POLE.
- AZ. 260° - 89.69° - SET NOTCH IN EAST END 24" CMP CULVERT.
- AZ. 310° - 78.07° - SET P.K. NAIL W/MONUMENTATION TAG IN SOUTH FACE UTILITY POLE.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 11-4-97  
  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by Robert H. Birkett Date 12/10/97  
 Surveyor's Michigan License No. 41094